



**US Army Corps
of Engineers®**
Philadelphia District

PROJECT FACT SHEET

Manasquan River, NJ

September 2005

CONGRESSIONAL INFO: Sen. Corzine NJ, Sen. Lautenberg NJ, Rep. Saxton NJ-3
Rep. Smith NJ-4

ACTIVITY: O & M, General

TYPE: Navigation

LOCATION: Project is located along the Atlantic Coast on the boundary between Atlantic and Ocean County, New Jersey.

PROJECT DESCRIPTION: This project provides for a channel 14 feet deep and 250 feet wide, protected by jetties and bulkheads, from the Atlantic Ocean to the inshore end of the north jetty; thence 12 feet deep and 300 feet wide to within 300 feet of the New York and Long Branch RR Bridge. The channel is approximately 1.5 miles long.

PROJECT STATUS: Jetty rehabilitation was completed in October 1997 using \$700,000 in FY 97 funds. Emergency maintenance dredging was accomplished in March 2003. Maintenance dredging is scheduled in FY 2005 with the government dredge.

FINANCIAL DATA: (\$000)

WORK ITEMS	FY 2003	FY 2004	FY 2005	FY 2006*
Dredging	84.0	190.0	190.0	510.0
TOTAL	84.0	190.0	190.0	510.0

* President's Budget

PROJECT MANAGER: Austin Gerrard
(215) 656-6737
austin.l.gerrard@usace.army.mil