










Geocell Systems Inc.

FLOOD WALL ESTIMATING SHEET

Suite 202
Pier 54, Terry Francois Blvd.
San Francisco, CA 94107-1220
Phone: 415-541-5300
Fax: 415-541-5369
email: info@geocellsystems.com

500 ← ENTER LINEAR FEET OF RDFW WALL REQUIRED

RDFW UNITS ARE 48" X 53" COLLAPSED, AND 48" X 52" X 8" TALL EXPANDED. WHEN EXPANDED, THE RDFW SAND FILLED AREA IS 42" X 42" X 8" TALL
RDFW UNITS MAY BE CUT TO FIT

ITEM DESCRIPTION	Layers	Height	Units Required	Containers	CU/YDS SAND	CU/YDS PER LF	ACTUAL LENGTH OF RDFW WALL
	1	8 Inches High	143	1.4	42.82	0.09	500.50
	2	16 Inches High	286	2.9	85.64	0.17	500.50
	3	24 Inches High	429	4.3	128.46	0.26	500.50
	4	32 Inches High	572	5.7	171.28	0.34	500.50
	5	40 Inches High	715	7.2	214.10	0.43	500.50
	6	48 Inches High	858	8.6	256.92	0.52	500.50
	7	56 inches High	1,001	10.0	299.74	0.60	500.50